BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Item No.

Name of Work : Improvement of Roads and Drains from Gangamma Temple to Kodigehalli Main Road in ward No. 08 (Kodigehalli) Kodigehalli sub division.

Sl. No	Approved Quantity	Description	Unit	Sanctioned Rates In Figures	Rates In Words
1	225.60	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 125/ Item No. 19.1/ PWD SR 2013-14	cum	65.88	
2	161.00	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 141 (SR 2013-14)	cum	78.24	
3	169.20	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2013-14	Cum	4290.84	
4	112.80	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 19/ Item No. 4.48/ PWD SR 2013-14	Cum	6464.88	

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Signature of the Contractor
Reg. No.
Postal Address

ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡಿದಂತೆ/
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ ..... Nil .....

Superintending Engineer 31/10/2013
Yelahanka Zone
BBMP, Bangalore-92